

AD-A104 654

HORNER AND SHIFRIN INC ST LOUIS MO

NATIONAL DAM SAFETY PROGRAM. WINDY KNOLL LAKE DAM (MO 30512), M--ETC(U)

SEP 80

F/G 13/13

DACW43-80-C-0063

NL

UNCLASSIFIED

1 OF 1
AD A
10-48-2

END
DATE
FILMED
10-81
DTIC

LEVEL ~~///~~

②

AD A104654

③ **MISSOURI - KANSAS CITY BASIN**

④ **WINDY KNOLL LAKE DAM**
⑤ **WARREN COUNTY, MISSOURI**
MO 30512

DTIC
ELECTE
S **D**
SEP 28 1981
H

⑥ **PHASE 1 INSPECTION REPORT**
NATIONAL DAM SAFETY PROGRAM



United States Army
Corps of Engineers
... Serving the Army
... Serving the Nation

St. Louis District

"Original contains color
plates: All DTIC reproductions
will be in black and
white"

PREPARED BY: U.S. ARMY ENGINEER DISTRICT, ST. LOUIS
FOR: STATE OF MISSOURI

81 9 28 066

SEPTEMBER 1980

DTIC FILE COPY

712

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

REPORT DOCUMENTATION PAGE		READ INSTRUCTIONS BEFORE COMPLETING FORM
1. REPORT NUMBER	2. GOVT ACCESSION NO. <i>A.D.-A104 654</i>	3. RECIPIENT'S CATALOG NUMBER
4. TITLE (and Subtitle) Phase I Dam Inspection Report National Dam Safety Program Windy Knoll Lake Dam (MO 30512) Warren County, Missouri		5. TYPE OF REPORT & PERIOD COVERED Final Report
7. AUTHOR(s) Horner & Shifrin, Inc.		6. PERFORMING ORG. REPORT NUMBER
9. PERFORMING ORGANIZATION NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		8. CONTRACT OR GRANT NUMBER(s) DACW43-80-C-0063 <i>WCU</i>
11. CONTROLLING OFFICE NAME AND ADDRESS U.S. Army Engineer District, St. Louis Dam Inventory and Inspection Section, LMSED-PD 210 Tucker Blvd., North, St. Louis, Mo. 63101		10. PROGRAM ELEMENT, PROJECT, TASK AREA & WORK UNIT NUMBERS <i>51</i>
14. MONITORING AGENCY NAME & ADDRESS (if different from Controlling Office) National Dam Safety Program, Windy Knoll Lake Dam (MO 30512), Missouri - Kansas City Basin, Warren County, Missouri. Phase I Inspection Report.		12. REPORT DATE September 1980
		13. NUMBER OF PAGES Approximately 40
		15. SECURITY CLASS. (of this report) UNCLASSIFIED
16. DISTRIBUTION Approved for release; distribution unlimited.		5a. DECLASSIFICATION/DOWNGRADING SCHEDULE
17. DISTRIBUTION STATEMENT (of the abstract entered in Block 20, if different from Report)		
18. SUPPLEMENTARY NOTES		
19. KEY WORDS (Continue on reverse side if necessary and identify by block number) Dam Safety, Lake, Dam Inspection, Private Dams		
20. ABSTRACT (Continue on reverse side if necessary and identify by block number) This report was prepared under the National Program of Inspection of Non-Federal Dams. This report assesses the general condition of the dam with respect to safety, based on available data and on visual inspection, to determine if the dam poses hazards to human life or property. <i>7/12-55</i>		


DD FORM 1 JAN 73 1473

EDITION OF 1 NOV 65 IS OBSOLETE

UNCLASSIFIED

SECURITY CLASSIFICATION OF THIS PAGE (When Data Entered)

SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)



SECURITY CLASSIFICATION OF THIS PAGE(When Data Entered)

MISSOURI - KANSAS CITY BASIN

**WINDY KNOLL LAKE DAM
WARREN COUNTY, MISSOURI
MO 30512**

PHASE 1 INSPECTION REPORT NATIONAL DAM SAFETY PROGRAM



**United States Army
Corps of Engineers**
*... Serving the Army
... Serving the Nation*

St. Louis District

**PREPARED BY: U.S. ARMY ENGINEER DISTRICT, ST. LOUIS
FOR: STATE OF MISSOURI**

SEPTEMBER 1980



REPLY TO
ATTENTION OF

DEPARTMENT OF THE ARMY
ST. LOUIS DISTRICT, CORPS OF ENGINEERS
210 TUCKER BOULEVARD, NORTH
ST. LOUIS, MISSOURI 63101

LMSD-P

SUBJECT: Windy Knoll Lake Dam, MO 30512, Phase I Inspection Report

This report presents the results of field inspection and evaluation of the Windy Knoll Lake Dam, MO 30512. It was prepared under the National Program of Inspection of Non-Federal Dams.

SUBMITTED BY: SIGNED
Chief, Engineering Division

25 SEP 1980

Date

APPROVED BY: SIGNED
Colonel, CE, District Engineer

25 SEP 1980

Date

Accession For	<input checked="" type="checkbox"/>
NTIS GRA&I	<input type="checkbox"/>
DTIC TAB	<input type="checkbox"/>
Unannounced	<input type="checkbox"/>
Justification	<input type="checkbox"/>
By	
Distribution/	
Availability	
Date	
A	

WINDY KNOLL LAKE DAM
MISSOURI INVENTORY NO. 30512
WARREN COUNTY, MISSOURI

PHASE I INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

PREPARED BY:

HORNER & SHIFRIN, INC.
5200 OAKLAND AVENUE
ST. LOUIS, MISSOURI 63110

FOR:

U. S. ARMY ENGINEER DISTRICT, ST. LOUIS
CORPS OF ENGINEERS

SEPTEMBER 1980

HS-8011

PHASE I REPORT

NATIONAL DAM SAFETY PROGRAM

Name of Dam: Windy Knoll Lake Dam

State Located: Missouri

County Located: Warren

Stream: Subtributary of Charrette Creek

Date of Inspection: 9 June 1980

The Windy Knoll Lake Dam was visually inspected by engineering personnel of Horner & Shifrin, Inc., Consulting Engineers, St. Louis, Missouri. The purpose of this inspection was to assess the general condition of the dam with respect to safety and, based upon this inspection and available data, determine if the dam poses a hazard to human life or property.

The following summarizes the findings of the visual inspection and the results of certain hydrologic/hydraulic investigations performed under the direction of the inspection team. Based on the visual inspection and the results of the hydrologic/hydraulic investigations, the present general condition of the dam is considered to be somewhat less than satisfactory. The following deficiencies were noticed during the inspection and are considered to have an adverse effect on the overall safety and future operation of the dam:

1. Numerous trees up to 4 inches in size exist on the downstream face of the dam. Patches of brushy undergrowth were also found on the downstream slope near the toe of the dam at the original stream location. Tree roots can provide passageways for lake seepage which

could lead to a piping condition (progressive internal erosion) resulting in failure of the dam. Brush may conceal animal burrows which could also provide passageways for lake seepage.

2. Erosion of the grass covered upstream face of the dam apparently by wave action and/or fluctuations of the lake surface level has created a near vertical bank up to about 12 inches high at the normal waterline. A grass covered slope is not considered adequate protection to prevent erosion by wave action or fluctuations of the lake level.
3. Surface cracks that appear to be due to drying of the soil, some as wide as 1 inch, as deep as 10 inches, and 4 feet in length, exist throughout most of the crest of the dam and particularly in areas where the turf cover is marginal. Surface cracking can promote erosion of the dam.


According to the criteria set forth in the recommended guidelines, the magnitude of the spillway design flood for the Windy Knoll Lake Dam, which is classified as small in size and of high hazard potential, is specified to be a minimum of one-half the Probable Maximum Flood (PMF). Considering the fact that a series of manmade lakes; Lake Sheffborg, Lake Lucern, and Lake Innsbrook, lie within the possible flood damage zone for this dam, and since failure of this dam by overtopping could result in successive failure of the three downstream dams which would endanger the lives of a number of people with dwellings about these lakes as well as those persons living within the downstream flood damage zone, it is recommended that the spillway for this dam be designed for the PMF. The Probable Maximum Flood (PMF) is the flood that may be expected from the most severe combination of critical meteorologic and hydrologic conditions that are reasonably possible in the region. The PMF is ordinarily accepted as the inflow design flood for dams where failure of the structure would increase the danger to human life.

Results of a hydrologic/hydraulic analysis indicated that the spillway is inadequate to pass lake outflow resulting from a storm of PMF magnitude. The spillway is capable of passing lake outflow corresponding to about 55 percent

of the PMF lake inflow and the lake outflow resulting from the 1 percent chance (100-year frequency) flood. According to the St. Louis District, Corps of Engineers, the length of the downstream damage zone, should failure of the dam occur, is estimated to be two miles. Accordingly, within the possible damage zone are portions of the Innsbrook Subdivision development including three dams and several dwellings along the shore of the lake upstream of Dam No. 31442. These dams (Nos. 31442, 30519 and 11243), according to the Corps of Engineers, have a high hazard classification.


A review of available data did not disclose that seepage or stability analyses of the dam were performed. This is considered a deficiency and should be rectified.

It is recommended that the Owner take the necessary action in the near future to correct or control the deficiencies and safety defects reported herein.



Ralph E. Sauthoff

P. E. Missouri E-19090



Albert B. Becker, Jr.

P. E. Missouri E-9168



OVERVIEW WINDY KNOLL LAKE DAM

PHASE 1 INSPECTION REPORT
NATIONAL DAM SAFETY PROGRAM

WINDY KNOLL LAKE DAM - MO 30512

TABLE OF CONTENTS

<u>Paragraph No.</u>	<u>Title</u>	<u>Page No.</u>
SECTION 1 - PROJECT INFORMATION		
1.1	General	1-1
1.2	Description of Project	1-1
1.3	Pertinent Data	1-3
SECTION 2 - ENGINEERING DATA		
2.1	Design	2-1
2.2	Construction	2-1
2.3	Operation	2-1
2.4	Evaluation	2-1
SECTION 3 - VISUAL INSPECTION		
3.1	Findings	3-1
3.2	Evaluation	3-3
SECTION 4 - OPERATIONAL PROCEDURES		
4.1	Procedures	4-1
4.2	Maintenance of Dam	4-1
4.3	Maintenance of Outlet Operating Facilities	4-1
4.4	Description of Any Warning Systems in Effect	4-1
4.5	Evaluation	4-1

<u>Paragraph No.</u>	<u>Title</u>	<u>Page No.</u>
	SECTION 5 - HYDRAULIC/HYDROLOGIC	
5.1	Evaluation of Features	5-1
	SECTION 6 - STRUCTURAL STABILITY	
6.1	Evaluation of Structural Stability	6-1
	SECTION 7 - ASSESSMENT/REMEDIAL MEASURES	
7.1	Dam Assessment	7-1
7.2	Remedial Measures	7-2

LIST OF PLATES

<u>Plate No.</u>	<u>Title</u>
1	Regional Vicinity Map
2	Lake Watershed Map
3	Dam Plan and Profile
4	Dam Cross-Section & Spillway Profile

APPENDIX A - INSPECTION PHOTOGRAPHS

<u>Page No.</u>	<u>Title</u>
A-1 thru A-3	Inspection Photographs

APPENDIX B - HYDROLOGIC AND HYDRAULIC ANALYSES

<u>Page No.</u>	<u>Title</u>
B-1 and B-2	Hydrologic & Hydraulic Computations
B-3 thru B-5	Computer Input Data
B-6 thru B-10	Computer Output Data
B-10	Lake Surface Area, Storage Volume and Elevation; Summary of Dam Safety Analysis

PHASE I INSPECTION REPORT

NATIONAL DAM SAFETY PROGRAM

WINDY KNOLL LAKE DAM - MO 30512

SECTION I - PROJECT INFORMATION

1.1 GENERAL

a. Authority. The National Dam Inspection Act, Public Law 92-367, dated 8 August 1972, authorized the Secretary of the Army, through the Corps of Engineers, to initiate a program of safety inspection of dams throughout the United States. Pursuant to the above, the St. Louis District, Corps of Engineers, directed that a safety inspection of the Windy Knoll Lake Dam be made.

b. Purpose of Inspection. The purpose of this visual inspection was to make an assessment of the general condition of the dam with respect to safety and, based upon available data and this inspection, determine if the dam poses a hazard to human life or property.

c. Evaluation Criteria. This evaluation was performed in accordance with the "Phase I" investigation procedures as prescribed in "Recommended Guidelines for Safety Inspection of Dams", Appendix D to "Report to the Chief of Engineers on the National Program of Inspection of Non-Federal Dams", dated May 1975.

1.2 DESCRIPTION OF PROJECT

a. Description of Dam and Appurtenances. The Windy Knoll Lake Dam is an earthfill type embankment rising approximately 35 feet above the natural streambed at the downstream toe of the barrier. The embankment has an upstream slope of approximately 1v on 3.7h, a crest width of about 12 feet,

and a downstream slope on the order of 1v on 3.1h. At the location of the original stream channel and at an elevation approximately 20 feet below the dam crest, the downstream slope flattens to about 1v on 5.2h. The length of the dam is approximately 462 feet. A plan and profile of the dam are shown on Plate 3 and a cross-section of the dam is shown on Plate 4. At normal pool elevation the reservoir impounded by the dam occupies approximately 7 acres. There is no drain line to dewater the lake.

The spillway, an excavated earth section, is located at the left, or east, abutment. The spillway outlet channel, an excavated earthen trapezoidal section, is cut into the hillside of the abutment. An earth bank constructed on the right side serves to confine flow to the channel. The channel extends approximately 75 feet from the centerline of the dam where it joins the natural drainage course of the adjacent watershed. This tributary meets the original stream on which the dam is constructed at a point about 125 feet downstream of the dam. Stone riprap up to about 6 inches in size covers most of the spillway outlet channel invert through the improved section. A cross-section of the spillway is shown on Plate 4.

b. Location. The dam is located on an unnamed subtributary of Charrette Creek, about 1 mile south and just west of the intersection of Muenz Road and State Highway M, and approximately 4 miles southwest of Wright City, Missouri, as shown on the Regional Vicinity Map, Plate 1. The dam is located in the southwest quadrant of Section 32, Township 47 North, Range 1 West, within Warren County.

c. Size Classification. The size classification based on the height of the dam and storage capacity, is categorized as small (per Table 1, Recommended Guidelines for Safety Inspection of Dams).

d. Hazard Classification. The Windy Knoll Lake Dam, according to the St. Louis District, Corps of Engineers, has a high hazard potential, meaning that if the dam should fail, there may be loss of life, serious damage to homes, or extensive damage to agricultural, industrial and commercial facilities, important public utilities, main highways, or railroads. The estimated flood damage zone, should failure of the dam occur, as determined by

the St. Louis District, extends two miles downstream of the dam. Within the possible flood damage zone are portions of the Innsbrook Subdivision development including three dams and several dwellings along the shore of the lake upstream of Dam No. 31442. These dams (Nos. 31442, 30519 and 11243), according to the Corps of Engineers, have a high hazard classification. Those features lying within the downstream damage zone reported by the Corps of Engineers, St. Louis District, were verified by the inspection team.

e. Ownership. The lake and dam are owned by the Willmarjim Company, a Missouri Corporation. The President of the company is Mr. William F. Sheff. Mr. Sheff's address is 5757 Manchester Avenue, St. Louis, Missouri 63110.

f. Purpose of Dam. The dam impounds water for recreational use.

g. Design and Construction History. According to the Owner, the dam was designed and constructed in about 1969 by Russell Bolinger, a local contractor and builder of earthen dams. Mr. Bolinger is deceased. The Owner reported that prior to construction of the dam, the proposed site was investigated by a representative of the Missouri Geological Survey and that test borings were obtained at the site of the proposed dam. However, records of these investigations, the test borings, and the design of the dam by Mr. Bolinger were unavailable.

h. Normal Operational Procedure. The lake level is unregulated. Lake outflow is governed by the capacity of an excavated earth type spillway.

1.3 PERTINENT DATA

a. Drainage Area. The area tributary to the lake is essentially meadowland. The watershed above the dam amounts to approximately 48 acres. The watershed area is outlined on Plate 2.

b. Discharge at Damsite.

- (1) Estimated known maximum flood at damsite ... 11 cfs* (W.S.Elev. 770.4)
- (2) Spillway capacity ... 263 cfs.

c. Elevation (Ft. above MSL). The following elevations were determined by survey and are based on the elevation of the lake, assumed to be the normal pool level, as shown on the 1972 Wright City, Missouri, Quadrangle Map, 7.5 Minute Series.

- (1) Observed pool ... 769.8
- (2) Normal pool ... 770.0
- (3) Spillway crest ... 770.0
- (4) Maximum experienced pool ... 770.4*
- (5) Top of dam ... 772.4 (min.)
- (6) Streambed at centerline of dam ... 742+ (est.)
- (7) Maximum tailwater ... Unknown
- (8) Observed tailwater ... None

d. Reservoir.

- (1) Length at normal pool (Elev. 770.0) ... 900 ft.
- (2) Length at maximum pool (Elev. 772.4) ... 1,000 ft.

e. Storage.

- (1) Normal pool ... 63 ac. ft.
- (2) Top of dam (incremental) ... 17 ac. ft.

f. Reservoir Surface

- (1) Normal pool ... 7 acres
- (2) Top of dam (incremental) ... 1 acre

*Based on an estimate of depth of flow at spillway as observed by the Owner.

g. Dam. The height of the dam is defined to be the overall vertical distance from the lowest point of foundation surface at the downstream toe of the barrier, to the top of the dam.

- (1) Type ... Earthfill, homogeneous*
- (2) Length ... 462 ft.
- (3) Height ... 35 ft.
- (4) Top width ... 12 ft.
- (5) Side slopes
 - a. Upstream ... 1v on 3.7h (above waterline)
 - b. Downstream ... 1v on 3.1h to 1v on 5.2h
- (6) Cutoff ... Core trench*
- (7) Slope protection
 - a. Upstream ... Grass
 - b. Downstream ... Grass

h. Spillway.

- (1) Type ... Uncontrolled, excavated earth
- (2) Location ... Left abutment
- (3) Crest ... Elevation 770.0
- (4) Approach channel ... Lake
- (5) Outlet channel ... Excavated earth, trapezoidal section

i. Emergency Spillway ... None

j. Lake Drawdown Facility ... None

*Per Owner

SECTION 2 - ENGINEERING DATA

2.1 DESIGN

Data relating to the design of the dam was unavailable.

2.2 CONSTRUCTION

As previously stated, the dam was constructed about 1969 by Russell Bolinger, a local contractor and builder of dams. According to the Owner, a core trench for seepage cutoff was excavated along the axis of the dam and that seams of shale were encountered during excavation of the trench. The Owner reported that the material used to backfill the trench and construct the dam was clay that was selected from areas to be occupied by the lake. The Owner also recalled that the embankment material was compacted using a sheepsfoot roller. No records of the construction of the dam were available.

2.3 OPERATION

The lake level is uncontrolled and governed by the elevation of the crest of an excavated earth type spillway. No indication was found that the dam has been overtopped. The Owner reported that the dam has never been overtopped and that the highest lake level experienced to date produced a depth of flow at the spillway estimated to be about 5 inches.

2.4 EVALUATION

a. Availability. Engineering data for assessing the design of the dam and spillway were unavailable.

b. Adequacy. No data available. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency. These seepage and stability analyses should be performed for appropriate loading conditions (including earthquake loads) and made a matter of record.

SECTION 3 - VISUAL INSPECTION

3.1 FINDINGS

a. General. A visual inspection of the Windy Knoll Lake Dam was made by Horner & Shifrin engineering personnel, R. E. Sauthoff, Civil Engineer, and A. B. Becker, Jr., Civil and Soils Engineer, on 9 June 1980. An examination of the dam area was also made by an engineering geologist, Jerry D. Higgins, Ph.D., a consultant retained by Horner & Shifrin for the purpose of assessing the site geology. Also examined at the time of the inspection, were the areas and features below the dam within the potential flood damage zone. Photographs of the dam taken at the time of the inspection are included on Pages A-1 through A-3 of Appendix A. The locations of the photographs taken during the inspection are indicated on Plate 3.

b. Site Geology. The dam site is located near the southern edge of the Dissected Till Plains Section of the Central Lowlands Physiographic Province and the northern edge of the Ozark Plateaus Physiographic Province. The topography is gently rolling with only 60 to 70 feet of relief between the reservoir and the surrounding drainage divides. No bedrock outcrops were noted at the site; however, nearby borings indicate over 100 feet of loess and glacial drift underlain by Ordovician-age sedimentary rock of the Kimmswick formation. The bedrock is gently dipping to the north, and no faults were observed or reported at the site.

The Kimmswick formation is a light gray, coarsely crystalline, medium-bedded to massive limestone. Weathered exposures characteristically appear pitted. The limestones are susceptible to solution weathering and may have solution-enlarged joints and bedding planes, sinkholes, etc. Often the karst features are filled with Pennsylvanian-age rubble.

The unconsolidated surficial materials consist of thick deposits of loess overlying glacial drift. The dam and reservoir are located on soils of the Keswick series. These soils are deep, moderately well-drained materials formed from loessal deposits. They are dark grayish brown silts near the

surface and become more clayey with depth. According to the Unified Soil Classification System, the soils are classified CL or CL-ML materials, are low in permeability, and are susceptible to erosion. The silty soils of the Hatton series cap the ridges above the reservoir. These soils formed from loess deposits and exhibit engineering properties similar to the Keswick soils. Glacial till overlain with loess was noted in the stream channel immediately downstream from the dam. The till consisted primarily of blocky clay with chert gravel and large glacial erratics.

There appear to be no significant geotechnical problems at the dam site. No adverse geologic conditions were observed that would be considered to severely affect the performance of the dam or reservoir.

c. Dam. The visible portions of the upstream and downstream faces of the dam (see Photos 1 and 2) as well as the dam crest, were inspected and except for surface cracks in the dam crest and some minor erosion of the upstream face at the waterline, appeared to be in sound condition. No settlement of the crest, sloughing of the slopes, or misalignment of the dam were noted. The surface cracks in the dam crest were random in direction and were found throughout the entire length of the dam. Cracks up to 1 inch in width (see Photo 5), 10 inches in depth, and about 4 feet in length were observed. Erosion, apparently by wave action, had created a near vertical bank up to 12 inches high at the normal waterline. No animal burrows were found in the face of the dam, but it did appear that several burrows had existed at some prior time.

Trees up to about 4 inches in diameter were found on the downstream face of the dam (see Photos 2 and 6), and at the downstream toe of the dam in the vicinity of the original stream channel, the undergrowth was quite dense. No seepage was noticed; however, due to the presence of dense undergrowth at the toe of the dam, not all areas could be thoroughly examined. Except for the dam crest which had been recently mowed, the grass on the dam was about 30 inches high at the time of the inspection. Examination of a soil sample obtained from the dam surface indicated the material to be a yellow-brown, silty lean clay (CL) of low-to-medium plasticity.

The excavated earth spillway (see Photos 3 and 4), except for some erosion of the invert at the junction of the spillway and the downstream channel, appeared to be in satisfactory condition. The invert of the spillway channel was protected from erosion by stone riprap up to about 6 inches in size. The eroded area of the channel was about 3 feet deep and up to 6 feet wide.

d. Downstream Channel. At a point approximately 700 feet downstream of the dam, the downstream channel, an unimproved section, joins Lake Scheffborg. Lake Scheffborg is the first of three manmade, tandem oriented, lakes located on the tributary just downstream of the dam. The other two lakes in succession are Lake Lucern and Lake Innsbrook. The dam for Lake Scheffborg which has a surface area of about 10 acres, lies approximately 0.35 miles downstream of the Windy Knoll Dam; the dam for Lake Lucern, a lake with a surface area of about 42 acres, lies about 1.0 mile downstream; and the dam for Lake Innsbrook, a lake with a surface area of almost 55 acres, lies approximately 1.6 miles downstream. The stream tributary joins Charrette Creek at a point about 1.0 mile downstream of the Lake Innsbrook Dam.

e. Reservoir. At the time of the inspection, the reservoir was near normal level and clear. No erosion of the lake banks was evident. For the most part, the area about the lake is meadowland. The amount of sediment within the lake could not be determined during the inspection; however, due to the vegetation covering the surrounding area, it is not expected to be significant.

3.2 EVALUATION

The deficiencies observed during the inspection and noted herein, are not considered of significant importance to warrant immediate remedial action, but should be rectified in the near future.

SECTION 4 - OPERATIONAL PROCEDURES

4.1 PROCEDURES

The spillway is uncontrolled. The lake surface level is governed by precipitation runoff, evaporation, seepage, and the capacity of the uncontrolled spillway.

4.2 MAINTENANCE OF DAM

According to the Owner, the dam receives periodic routine maintenance such as mowing of the grass on the dam crest, yearly removal by trapping of muskrats, and additions of riprap to the invert of the spillway channel.

4.3 MAINTENANCE OF OUTLET OPERATING FACILITIES

No outlet facilities requiring operation exist at this dam, and there is no reservoir regulation plan.

4.4 DESCRIPTION OF ANY WARNING SYSTEMS IN EFFECT

The inspection did not reveal the existence of a dam failure warning system.

4.5 EVALUATION

It is recommended that maintenance of the dam also include removal of trees and periodic cutting of grass on the slopes. Measures should also be taken to prevent further erosion of the upstream face at the normal waterline. It is also recommended that a detailed inspection of the dam be instituted on a regular basis by an engineer experienced in the design and construction of dams and that records be kept of all inspections made and remedial measures taken.

SECTION 5 - HYDRAULIC/HYDROLOGIC

5.1 EVALUATION OF FEATURES

a. Design Data. Design data are not available.

b. Experience Data. The drainage area and lake surface area were determined from the 1972 USGS Wright City, Missouri, Quadrangle Map. The proportions and dimensions of the spillway and dam were developed from surveys made during the inspection. Records of rainfall, streamflow, or flood data for the watershed were not available.

According to the St. Louis District, Corps of Engineers, the estimated flood damage zone, should failure of the dam occur, extends 2 miles downstream of the dam. The dams for Lake Scheffborg, Lake Lucern, and Lake Innsbrook, all of which are classified as high hazard by the Corps of Engineers, lie within the flood damage zone.

c. Visual Observations.

(1) The spillway, a shallow, broad-crested, excavated earth, trapezoidal section, is located at the left abutment.

(2) Spillway releases within the capacity of the spillway outlet should not endanger the dam.

(3) The original stream channel abuts the toe of the dam.

d. Overtopping Potential. The spillway is inadequate to pass the probable maximum flood, without overtopping the dam. The spillway is adequate, however, to pass one-half the probable maximum flood without overtopping the dam. The results of the dam overtopping analyses are as follows:

(Note: The data appearing in the following table were extracted from the computer output data appearing in Appendix B. Decimal values have been rounded to the nearest one-tenth in order to prevent assumption of unwarranted accuracy.)

<u>Ratio of PMF</u>	<u>Q-Peak Outflow (cfs)</u>	<u>Max Lake W.S. Elev.</u>	<u>Max. Depth (Ft.) of Flow over Dam (Elev. 772.4)</u>	<u>Duration of Overtopping of Dam (Hours)</u>
0.50	238	772.3	0.0	0.0
1.00	620	773.6	1.2	0.9

Elevation 772.4 was found to be the lowest point in the dam crest. The flow safely passing the spillway just prior to overtopping was determined to be approximately 263 cfs, which is the routed outflow corresponding to about 55 percent of the probable maximum flood inflow. During peak flow of the probable maximum flood, the greatest depth of flow over the dam is projected to be 1.2 feet and overtopping will extend across the entire length of the dam.

e. Evaluation. Experience with embankments constructed of similar material (a silty lean clay of low-to-medium plasticity) to that used to construct this dam has shown evidence that under certain conditions such as high velocity flow, the material can be very erodible. Such a condition exists during the PMF when large lake outflow, accompanied by high flow velocities, occurs. For the PMF condition where the depth of flow over the dam crest, a maximum of 1.2 feet, and the duration of flow over the dam, 0.9 hours, are considerable, damage by erosion to the crest and downstream face of the dam is expected. The extent of these damages is not predictable; however, there is a possibility that they could result in failure by erosion of the dam.

f. References. Procedures and data for determining the probable maximum flood, the 100-year frequency flood, and the discharge rating curve for flow passing the spillway and dam crest are presented on pages B-1 and B-2 of the

Appendix. Listings of the HEC-1 (Dam Safety Version) input data for both the probable maximum flood and the 100-year frequency flood are shown on pages B-3 through B-5. Computer output data, including unit hydrograph ordinates, tabulation of PMF rainfall, loss and inflow data are shown on pages B-6 through B-9; tabulation of lake surface area, elevation and storage volume is shown on page B-10 and tabulations titled "Summary of Dam Safety Analysis" for the PMF and 1 percent chance (100-year frequency) flood are also shown on page B-10.

SECTION 6 - STRUCTURAL STABILITY

6.1 EVALUATION OF STRUCTURAL STABILITY

a. Visual Observations. Visual observations of conditions which adversely affect the structural stability of the dam are discussed in Section 3, paragraph 3.1c.

b. Design and Construction Data. No design or construction data relating to the structural stability of the dam are known to exist. Seepage and stability analyses comparable to the requirements of the "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency. These seepage and stability analyses should be performed for appropriate loading conditions (including earthquake loads) and made a matter of record.

c. Operating Records. No appurtenant structures or facilities requiring operation exist at this dam. According to the Owner, no records are kept of the lake level, spillway discharge, dam settlement, or seepage.

d. Post Construction Changes. According to the Owner, no post construction changes have been made or have occurred which would affect the structural stability of the dam.

e. Seismic Stability. The dam is located in an area close to the boundary separating the Zone I and Zone II seismic probability areas. An earthquake of the magnitude that might occur in this area would not be expected to cause structural damage to a well constructed earth dam of this size provided that static stability conditions are satisfactory and conventional safety margins exist. However, it is recommended that the prescribed seismic loading be applied in any stability analyses performed for this dam.

SECTION 7 - ASSESSMENT/REMEDIAL MEASURES

7.1 DAM ASSESSMENT

a. Safety. A hydraulic analysis indicated that the spillway is capable of passing lake outflow of about 263 cfs without the level of the lake exceeding the low point in the top of the dam. A hydrologic analysis of the lake watershed area, as discussed in Section 5, paragraph 5.1d, indicates that for storm runoff of probable maximum flood magnitude, the lake outflow would be about 620 cfs, and that for the 1 percent chance (100-year frequency) flood, the lake outflow would be about 82 cfs.

Seepage and stability analyses of the dam were not available for review, and therefore, no judgment could be made with respect to the structural stability of the dam.

Several items were noticed during the inspection that could adversely affect the safety of the dam. These items include trees and brush on the downstream slope of the embankment, surface cracks in the dam crest, and the lack of adequate slope protection to prevent erosion of the upstream face of the dam.

b. Adequacy of Information. Due to lack of design and construction data, the assessments reported herein were based on external conditions as determined during the visual inspection. The assessments of the hydrology of the watershed and capacity of the spillway were based on a hydrologic/hydraulic study as indicated in Section 5. Seepage and stability analyses comparable to the requirements of "Recommended Guidelines for Safety Inspection of Dams" were not available, which is considered a deficiency.

c. Urgency. The remedial measures recommended in paragraph 7.2 for the items concerning the safety of the dam noted in paragraph 7.1a should be accomplished within the near future.

d. Necessity for Phase II. Based on the results of the Phase I inspection, a Phase II investigation is not recommended.

e. Seismic Stability. The dam is located in an area close to the boundary separating the Zone I and Zone II seismic probability areas. An earthquake of the magnitude that might occur in this area would not be expected to cause structural damage to a well constructed earth dam of this size provided that static stability conditions are satisfactory and conventional safety margins exist. However, it is recommended that the prescribed seismic loading be applied in any stability analyses performed for this dam.

7.2 REMEDIAL MEASURES

a. Recommendations. The following actions are recommended.

(1) Based upon criteria set forth in the recommended guidelines, spillway size and/or height of dam should be increased in order to pass lake outflow resulting from a storm of probable maximum flood magnitude. In either case, the spillway should be protected to prevent erosion.

(2) Obtain the necessary soil data and perform dam seepage and stability analyses in order to determine the structural stability of the dam for all operational conditions. Seepage and stability analyses should be performed by a qualified professional engineer experienced in the design and construction of earthen dams.

b. Operations and Maintenance (O & M) Procedures. The following O & M Procedures are recommended:



(1) Remove the trees and brushy type undergrowth that may conceal animal burrows from the downstream face of the dam. Tree roots and animal burrows can provide passageways for lake seepage that could lead to a piping condition and failure of the dam. The areas at the toe of the dam should be examined for animal burrows, sloughing, and other defects once they are cleared of undergrowth, etc.

(2) Provide some form of protection other than grass for the upstream face of the dam at and above the normal waterline in order to prevent erosion. A grass covered slope is not considered adequate protection to prevent erosion by wave action or by a fluctuating lake level.

(3) The areas of the dam crest that have only a marginal cover of grass should be provided with some type of durable plant cover to prevent cracking of the surface. Surface cracks can promote erosion of the dam.

(4) Provide maintenance of all areas of the dam and spillway on a regularly scheduled basis in order to insure features of being in satisfactory operational condition.

(5) A detailed inspection of the dam should be instituted on a regular basis by an engineer experienced in the design and construction of dams. It is also recommended, for future reference, that records be kept of all inspections made and remedial measures taken.




**WARREN
COUNTY**

LOCATION MAP


WINDY KNOLL LAKE DAM




REGIONAL VICINITY MAP



A=APPROXIMATE LIMIT OF DOWNSTREAM DAMAGE ZONE




WINDY KNOLL LAKE DAM




SCALE IN FEET
(CONTOUR INTERVAL 20 FEET)

LAKE WATERSHED MAP





GENERAL PLAN OF
SCALE: 1"=50'



PROFILE DAM CRE
SCALES: 1"=10' V., 1"=50'

6
PHOTO LOCATION & KEY
(SEE APPENDIX A)



FILE DAM CREST


SCALES: 1"=10' V., 1"=50' H.

WINDY KNOLL LAKE DAM
DAM PLAN & PROFILE


Horner & Shifrin, Inc.

July 1980


PLATE 3




CROSS-SECTION STA.
 SCALES: 1"=10' V., 1"=20'



PROFILE - SPILLWAY CHANNEL
 SCALES: 1"=10' V., 1"=20' H.



SECTION STA. 2+80
 SCALES: 1"=10' V., 1"=20' H.



CROSS-SECTION SPILLWAY
 SCALES: 1"=10' V., 1"=20' H.

WINDY KNOLL LAKE DAM
 DAM CROSS-SECTION &
 SPILLWAY PROFILE
 Horner & Shifrin, Inc. July 1980

12

APPENDIX A
INSPECTION PHOTOGRAPHS



NO. 1: UPSTREAM FACE OF DAM




NO. 2: DOWNSTREAM FACE OF DAM



NO. 3: SPILLWAY APPROACH AND CREST



NO. 4: SPILLWAY OUTLET CHANNEL - LOOKING
DOWNSTREAM FROM CREST



NO. 5: SURFACE CRACK IN CREST OF DAM



NO. 6: TREES (FOREGROUND) ON DOWNSTREAM FACE OF DAM

APPENDIX B

HYDROLOGIC AND HYDRAULIC ANALYSES

HYDROLOGIC AND HYDRAULIC COMPUTATIONS

1. The HEC-1 Dam Safety Version (July 1978, Modified 26 February 1979) program was used to develop inflow and outflow hydrographs and dam overtopping analyses, with hydrologic inputs as follows:

a. Probable maximum precipitation (200 sq. mile, 24-hour value equals 25.0 inches) from Hydrometeorological Report No. 33. The precipitation data used in the analysis of the 1 percent (100-year frequency) flood was provided by the St. Louis District, Corps of Engineers. Due to the fact that the watershed for this reservoir is small, the lake level was assumed to be at normal pool as a result of antecedent storms prior to occurrence of the PMF and the probabilistic storm.

b. Drainage area = 0.075 square miles = 48 acres.

c. SCS parameters:

$$\text{Time of Concentration } (T_c) = \left(\frac{11.9L^3}{H} \right)^{0.385} = 0.132 \text{ hours}$$

Where: T_c = Travel time of water from hydraulically most distant point to point of interest, hours

L = Length of longest watercourse = 0.284 miles

H = Elevation difference = 52 feet

The time of concentration (T_c) was obtained using Method C as described in Figure 30, "Design of Small Dams" by the United States Department of the Interior, Bureau of Reclamation, and was verified using average channel velocity estimates and watercourse lengths.

Lag Time = 0.079 hours (0.60 T_c)

Hydrologic Soil Group = 36% C and 64% D per SCS County Soil Report

Soil type CN = 80 (AMC II, 100-yr flood condition)
= 91 (AMC III, PMF condition)

2. The spillway section consists of a broad-crested, trapezoidal section for which conventional weir formulas do not apply.

Spillway release rates were determined as follows:

a. Spillway crest section properties (area, "a" and top width, "t") were computed for various depths, "d".

b. It was assumed that flow over the spillway crest would occur at critical depth. Flow at critical depth was computed as

$Q_c = (a_{tc}^3)^{0.5}$ for the various depths, "d". Corresponding velocities (v_c) and velocity heads (H_{vc}) were determined using conventional formulas.* Reference, "Handbook of Hydraulics", Fifth Edition, by King and Brater, page 8-7.

c. Static lake levels corresponding to the various flow values passing the spillway were computed as critical depths plus critical velocity heads ($d_c + H_{vc}$), and the relationship between lake level and spillway discharge was thus obtained. The procedure neglects the minor insignificant friction losses across the length of the spillway.

3. The profile of the dam crest is irregular and flow over the dam cannot be determined by application of conventional weir formulas. Crest length and elevation data for the dam crest proper were entered into the HEC-1 Program on the \$L and the \$V cards. The program assumes that flow over the dam crest section occurs at critical depth and computes internally the flow over the dam crest and adds this flow to the flow over the spillway as entered on the Y4 and Y5 cards.

*
$$v_c = \frac{Q_c}{a} ; H_{vc} = \frac{v_c^2}{2g}$$

ANALYSIS OF DAM OVERTOPPING USING RATIOS OF PMF											
HYDROLOGIC HYDRAULIC ANALYSIS OF SAFETY OF WINNY ENOLL LAKE DAM											
RATIOS OF PMF ROUTED THROUGH RESERVOIR											
1	PMF	0	5	0	0	0	0	0	0	0	0
2	PMF	0	5	0	0	0	0	0	0	0	0
3	PMF	0	5	0	0	0	0	0	0	0	0
4	PMF	0	5	0	0	0	0	0	0	0	0
5	PMF	0	5	0	0	0	0	0	0	0	0
6	PMF	0	5	0	0	0	0	0	0	0	0
7	PMF	0	5	0	0	0	0	0	0	0	0
8	PMF	0	5	0	0	0	0	0	0	0	0
9	PMF	0	5	0	0	0	0	0	0	0	0
10	PMF	0	5	0	0	0	0	0	0	0	0
11	PMF	0	5	0	0	0	0	0	0	0	0
12	PMF	0	5	0	0	0	0	0	0	0	0
13	PMF	0	5	0	0	0	0	0	0	0	0
14	PMF	0	5	0	0	0	0	0	0	0	0
15	PMF	0	5	0	0	0	0	0	0	0	0
16	PMF	0	5	0	0	0	0	0	0	0	0
17	PMF	0	5	0	0	0	0	0	0	0	0
18	PMF	0	5	0	0	0	0	0	0	0	0
19	PMF	0	5	0	0	0	0	0	0	0	0
20	PMF	0	5	0	0	0	0	0	0	0	0
21	PMF	0	5	0	0	0	0	0	0	0	0
22	PMF	0	5	0	0	0	0	0	0	0	0
23	PMF	0	5	0	0	0	0	0	0	0	0
24	PMF	0	5	0	0	0	0	0	0	0	0
25	PMF	0	5	0	0	0	0	0	0	0	0
26	PMF	0	5	0	0	0	0	0	0	0	0
27	PMF	0	5	0	0	0	0	0	0	0	0
28	PMF	0	5	0	0	0	0	0	0	0	0
29	PMF	0	5	0	0	0	0	0	0	0	0
30	PMF	0	5	0	0	0	0	0	0	0	0
31	PMF	0	5	0	0	0	0	0	0	0	0
32	PMF	0	5	0	0	0	0	0	0	0	0
33	PMF	0	5	0	0	0	0	0	0	0	0
34	PMF	0	5	0	0	0	0	0	0	0	0
35	PMF	0	5	0	0	0	0	0	0	0	0
36	PMF	0	5	0	0	0	0	0	0	0	0
37	PMF	0	5	0	0	0	0	0	0	0	0
38	PMF	0	5	0	0	0	0	0	0	0	0
39	PMF	0	5	0	0	0	0	0	0	0	0
40	PMF	0	5	0	0	0	0	0	0	0	0
41	PMF	0	5	0	0	0	0	0	0	0	0
42	PMF	0	5	0	0	0	0	0	0	0	0
43	PMF	0	5	0	0	0	0	0	0	0	0
44	PMF	0	5	0	0	0	0	0	0	0	0
45	PMF	0	5	0	0	0	0	0	0	0	0
46	PMF	0	5	0	0	0	0	0	0	0	0
47	PMF	0	5	0	0	0	0	0	0	0	0
48	PMF	0	5	0	0	0	0	0	0	0	0
49	PMF	0	5	0	0	0	0	0	0	0	0
50	PMF	0	5	0	0	0	0	0	0	0	0
51	PMF	0	5	0	0	0	0	0	0	0	0
52	PMF	0	5	0	0	0	0	0	0	0	0
53	PMF	0	5	0	0	0	0	0	0	0	0
54	PMF	0	5	0	0	0	0	0	0	0	0
55	PMF	0	5	0	0	0	0	0	0	0	0
56	PMF	0	5	0	0	0	0	0	0	0	0
57	PMF	0	5	0	0	0	0	0	0	0	0
58	PMF	0	5	0	0	0	0	0	0	0	0
59	PMF	0	5	0	0	0	0	0	0	0	0
60	PMF	0	5	0	0	0	0	0	0	0	0
61	PMF	0	5	0	0	0	0	0	0	0	0
62	PMF	0	5	0	0	0	0	0	0	0	0
63	PMF	0	5	0	0	0	0	0	0	0	0
64	PMF	0	5	0	0	0	0	0	0	0	0
65	PMF	0	5	0	0	0	0	0	0	0	0
66	PMF	0	5	0	0	0	0	0	0	0	0
67	PMF	0	5	0	0	0	0	0	0	0	0
68	PMF	0	5	0	0	0	0	0	0	0	0
69	PMF	0	5	0	0	0	0	0	0	0	0
70	PMF	0	5	0	0	0	0	0	0	0	0
71	PMF	0	5	0	0	0	0	0	0	0	0
72	PMF	0	5	0	0	0	0	0	0	0	0
73	PMF	0	5	0	0	0	0	0	0	0	0
74	PMF	0	5	0	0	0	0	0	0	0	0
75	PMF	0	5	0	0	0	0	0	0	0	0
76	PMF	0	5	0	0	0	0	0	0	0	0
77	PMF	0	5	0	0	0	0	0	0	0	0
78	PMF	0	5	0	0	0	0	0	0	0	0
79	PMF	0	5	0	0	0	0	0	0	0	0
80	PMF	0	5	0	0	0	0	0	0	0	0
81	PMF	0	5	0	0	0	0	0	0	0	0
82	PMF	0	5	0	0	0	0	0	0	0	0
83	PMF	0	5	0	0	0	0	0	0	0	0
84	PMF	0	5	0	0	0	0	0	0	0	0
85	PMF	0	5	0	0	0	0	0	0	0	0
86	PMF	0	5	0	0	0	0	0	0	0	0
87	PMF	0	5	0	0	0	0	0	0	0	0
88	PMF	0	5	0	0	0	0	0	0	0	0
89	PMF	0	5	0	0	0	0	0	0	0	0
90	PMF	0	5	0	0	0	0	0	0	0	0
91	PMF	0	5	0	0	0	0	0	0	0	0
92	PMF	0	5	0	0	0	0	0	0	0	0
93	PMF	0	5	0	0	0	0	0	0	0	0
94	PMF	0	5	0	0	0	0	0	0	0	0
95	PMF	0	5	0	0	0	0	0	0	0	0
96	PMF	0	5	0	0	0	0	0	0	0	0
97	PMF	0	5	0	0	0	0	0	0	0	0
98	PMF	0	5	0	0	0	0	0	0	0	0
99	PMF	0	5	0	0	0	0	0	0	0	0
100	PMF	0	5	0	0	0	0	0	0	0	0

THIS PAGE IS BEST QUALITY PRACTICE
FROM COPY FURNISHED TO DDC

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

[illegible]

THE COURT HAS THE HONOR

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

ANALYSIS OF DAM OVERTOPPING USING RATIOS OF PMF
HYDROLOGIC-HYDRAULIC ANALYSIS OF SAFETY OF WINDY KNOLL LAKE DAM
RATIOS OF PMF ROUTED THROUGH RESERVOIR

JOB SPECIFICATION

NO	NHR	NMIN	IDAY	IHR	IMIN	METRO	IPLT	IPRT	INSTAN
203	0	5	0	0	0	0	0	0	0
			JOPER	INT	LROPT	TRACE			
			5	0	0	0			

MULTI-PLAN ANALYSES TO BE PERFORMED
NPLAN= 1 NRTIO= 3 LRTIO= 1
RTIOS= .50 .55 1.00

SUB-AREA RUNOFF COMPUTATION

INFLOW HYDROGRAPH

ISTAG	ICOMP	IEDON	ITARE	UPLT	UPRT	INAME	ITAGE	IAUCO
INFLOW	0	0	0	0	0	1	0	0

HYDROGRAPH DATA

INHC	INXC	TAREA	SNAP	TREA	TSEF	RATIO	ITAG	ITAME	LOCAL
1	2	.03	0.00	.70	1.00	0.00	0	1	0

PRECIP DATA

SPFE	PM5	R6	R12	R24	R48	R72	R96
0.00	25.00	102.00	120.00	130.00	0.00	0.00	0.00

LOSS DATA

LROPT	STRIR	BLTKR	RTICL	ERAIN	STRMS	RTICH	STRTL	ONSTL	ALOM	RTIMP
0	0.00	0.00	1.00	0.00	0.00	1.00	-1.00	-91.00	0.00	0.00

CURVE NO = -91.00 WETNESS = -1.00 EFFECT CN = 01.00

UNIT HYDROGRAPH DATA

TC= 0.00 LAG= .06

RECESSION DATA

STRTO= -1.00 OROSH= -.10 RTIOB= 2.00

TIME INCREMENT TOO LARGE--(NHD IS GT LAG/2)

UNIT HYDROGRAPH 7 END OF PERIOD ORDINATES: TC= 0.00 HOURS: LAG= .06 VOL= 1.00

237.	234.	75.	24.	8.	3.	0.
------	------	-----	-----	----	----	----

0							END-OF-PERIOD FLOW						
MO.DA	HR.MM	PERIOD	RAIN	EXCS	LOSS	COMP 0	MO.DA	HR.MM	PERIOD	RAIN	EXCS	LOSS	COMP 0
1.01	.05	1	.01	0.00	.01	0.	1.01	12.05	145	.21	.21	.01	70.
1.01	.10	2	.01	0.00	.01	0.	1.01	12.10	146	.21	.21	.00	104.
1.01	.15	3	.01	0.00	.01	0.	1.01	12.15	147	.21	.21	.00	115.
1.01	.20	4	.01	0.00	.01	0.	1.01	12.20	148	.21	.21	.00	119.
1.01	.25	5	.01	0.00	.01	0.	1.01	12.25	149	.21	.21	.00	126.
1.01	.30	6	.01	0.00	.01	0.	1.01	12.30	150	.21	.21	.00	121.
1.01	.35	7	.01	0.00	.01	0.	1.01	12.35	151	.21	.21	.00	121.
1.01	.40	8	.01	0.00	.01	0.	1.01	12.40	152	.21	.21	.00	121.
1.01	.45	9	.01	0.00	.01	0.	1.01	12.45	153	.21	.21	.00	121.
1.01	.50	10	.01	0.00	.01	0.	1.01	12.50	154	.21	.21	.00	122.
1.01	.55	11	.01	0.00	.01	0.	1.01	12.55	155	.21	.21	.00	122.
1.01	1.00	12	.01	0.00	.01	0.	1.01	13.00	156	.21	.21	.00	122.
1.01	1.05	13	.01	0.00	.01	0.	1.01	13.05	157	.28	.25	.00	132.
1.01	1.10	14	.01	0.00	.01	0.	1.01	13.10	158	.28	.25	.00	141.
1.01	1.15	15	.01	.00	.01	0.	1.01	13.15	159	.28	.25	.00	145.
1.01	1.20	16	.01	.00	.01	0.	1.01	13.20	160	.28	.25	.00	148.
1.01	1.25	17	.01	.00	.01	0.	1.01	13.25	161	.28	.25	.00	146.
1.01	1.30	18	.01	.00	.01	1.	1.01	13.30	162	.28	.25	.00	147.
1.01	1.35	19	.01	.00	.01	1.	1.01	13.35	163	.28	.25	.00	147.
1.01	1.40	20	.01	.00	.01	1.	1.01	13.40	164	.28	.25	.00	147.
1.01	1.45	21	.01	.00	.01	1.	1.01	13.45	165	.28	.25	.00	147.
1.01	1.50	22	.01	.00	.01	1.	1.01	13.50	166	.28	.25	.00	147.
1.01	1.55	23	.01	.00	.01	1.	1.01	13.55	167	.28	.25	.00	147.
1.01	2.00	24	.01	.00	.01	2.	1.01	14.00	168	.32	.25	.00	147.
1.01	2.05	25	.01	.00	.01	2.	1.01	14.05	169	.32	.32	.00	152.
1.01	2.10	26	.01	.00	.01	2.	1.01	14.10	170	.32	.32	.00	157.
1.01	2.15	27	.01	.00	.01	2.	1.01	14.15	171	.32	.32	.00	162.
1.01	2.20	28	.01	.00	.01	2.	1.01	14.20	172	.32	.32	.00	163.
1.01	2.25	29	.01	.00	.01	2.	1.01	14.25	173	.32	.32	.00	164.
1.01	2.30	30	.01	.00	.01	2.	1.01	14.30	174	.32	.32	.00	164.
1.01	2.35	31	.01	.00	.01	3.	1.01	14.35	175	.32	.32	.00	164.
1.01	2.40	32	.01	.00	.01	3.	1.01	14.40	176	.32	.32	.00	164.
1.01	2.45	33	.01	.01	.01	3.	1.01	14.45	177	.32	.32	.00	164.
1.01	2.50	34	.01	.01	.01	3.	1.01	14.50	178	.32	.32	.00	164.
1.01	2.55	35	.01	.01	.01	3.	1.01	14.55	179	.32	.32	.00	164.
1.01	3.00	36	.01	.01	.01	3.	1.01	15.00	180	.32	.32	.00	164.
1.01	3.05	37	.01	.01	.01	3.	1.01	15.05	181	.39	.39	.00	155.
1.01	3.10	38	.01	.01	.01	3.	1.01	15.10	182	.39	.39	.00	171.
1.01	3.15	39	.01	.01	.01	3.	1.01	15.15	183	.39	.39	.00	197.
1.01	3.20	40	.01	.01	.01	4.	1.01	15.20	184	.58	.58	.00	204.
1.01	3.25	41	.01	.01	.01	4.	1.01	15.25	185	.58	.58	.00	202.
1.01	3.30	42	.01	.01	.01	4.	1.01	15.30	186	1.85	1.84	.00	803.
1.01	3.35	43	.01	.01	.01	4.	1.01	15.35	187	2.71	2.71	.01	1051.
1.01	3.40	44	.01	.01	.01	4.	1.01	15.40	188	1.07	1.06	.00	1029.
1.01	3.45	45	.01	.01	.01	4.	1.01	15.45	189	.68	.68	.00	658.
1.01	3.50	46	.01	.01	.01	4.	1.01	15.50	190	.53	.53	.00	456.
1.01	3.55	47	.01	.01	.01	4.	1.01	15.55	191	.39	.39	.00	336.
1.01	4.00	48	.01	.01	.01	4.	1.01	16.00	192	.39	.39	.00	250.

END-OF-PERIOD FLOW (Cont'd)

1.01	4.05	49	.01	.01	.01	4.	1.01	16.05	193	.30	.30	.00	213.
1.01	4.10	50	.01	.01	.01	4.	1.01	16.10	194	.30	.30	.00	185.
1.01	4.15	51	.01	.01	.01	4.	1.01	16.15	195	.30	.30	.00	176.
1.01	4.20	52	.01	.01	.01	5.	1.01	16.20	196	.30	.30	.00	174.
1.01	4.25	53	.01	.01	.01	5.	1.01	16.25	197	.30	.30	.00	173.
1.01	4.30	54	.01	.01	.01	5.	1.01	16.30	198	.30	.30	.00	173.
1.01	4.35	55	.01	.01	.01	5.	1.01	16.35	199	.30	.30	.00	172.
1.01	4.40	56	.01	.01	.01	5.	1.01	16.40	200	.30	.30	.00	172.
1.01	4.45	57	.01	.01	.01	5.	1.01	16.45	201	.30	.30	.00	172.
1.01	4.50	58	.01	.01	.01	5.	1.01	16.50	202	.30	.30	.00	172.
1.01	4.55	59	.01	.01	.01	5.	1.01	16.55	203	.30	.30	.00	172.
1.01	5.00	60	.01	.01	.01	5.	1.01	17.00	204	.30	.30	.00	172.
1.01	5.05	61	.01	.01	.01	5.	1.01	17.05	205	.23	.23	.00	157.
1.01	5.10	62	.01	.01	.01	5.	1.01	17.10	206	.23	.23	.00	143.
1.01	5.15	63	.01	.01	.00	5.	1.01	17.15	207	.23	.23	.00	136.
1.01	5.20	64	.01	.01	.00	5.	1.01	17.20	208	.23	.23	.00	136.
1.01	5.25	65	.01	.01	.00	5.	1.01	17.25	209	.23	.23	.00	136.
1.01	5.30	66	.01	.01	.00	5.	1.01	17.30	210	.23	.23	.00	136.
1.01	5.35	67	.01	.01	.00	5.	1.01	17.35	211	.23	.23	.00	136.
1.01	5.40	68	.01	.01	.00	5.	1.01	17.40	212	.23	.23	.00	136.
1.01	5.45	69	.01	.01	.00	5.	1.01	17.45	213	.23	.23	.00	136.
1.01	5.50	70	.01	.01	.00	5.	1.01	17.50	214	.23	.23	.00	136.
1.01	5.55	71	.01	.01	.00	6.	1.01	17.55	215	.23	.23	.00	136.
1.01	6.00	72	.01	.01	.00	6.	1.01	18.00	216	.23	.23	.00	136.
1.01	6.05	73	.06	.04	.02	14.	1.01	18.05	217	.02	.02	.00	108.
1.01	6.10	74	.06	.05	.02	22.	1.01	18.10	218	.02	.02	.00	99.
1.01	6.15	75	.06	.05	.02	25.	1.01	18.15	219	.02	.02	.00	92.
1.01	6.20	76	.06	.05	.02	27.	1.01	18.20	220	.02	.02	.00	86.
1.01	6.25	77	.06	.05	.01	27.	1.01	18.25	221	.02	.02	.00	80.
1.01	6.30	78	.06	.05	.01	28.	1.01	18.30	222	.02	.02	.00	75.
1.01	6.35	79	.06	.05	.01	29.	1.01	18.35	223	.02	.02	.00	70.
1.01	6.40	80	.06	.05	.01	29.	1.01	18.40	224	.02	.02	.00	65.
1.01	6.45	81	.06	.05	.01	29.	1.01	18.45	225	.02	.02	.00	61.
1.01	6.50	82	.06	.05	.01	30.	1.01	18.50	226	.02	.02	.00	57.
1.01	6.55	83	.06	.05	.01	30.	1.01	18.55	227	.02	.02	.00	53.
1.01	7.00	84	.06	.05	.01	30.	1.01	19.00	228	.02	.02	.00	49.
1.01	7.05	85	.06	.05	.01	31.	1.01	19.05	229	.02	.02	.00	45.
1.01	7.10	86	.06	.05	.01	31.	1.01	19.10	230	.02	.02	.00	43.
1.01	7.15	87	.06	.05	.01	31.	1.01	19.15	231	.02	.02	.00	40.
1.01	7.20	88	.06	.05	.01	31.	1.01	19.20	232	.02	.02	.00	37.
1.01	7.25	89	.06	.05	.01	31.	1.01	19.25	233	.02	.02	.00	35.
1.01	7.30	90	.06	.06	.01	32.	1.01	19.30	234	.02	.02	.00	35.
1.01	7.35	91	.06	.06	.01	32.	1.01	19.35	235	.02	.02	.00	33.
1.01	7.40	92	.06	.06	.01	32.	1.01	19.40	236	.02	.02	.00	33.
1.01	7.45	93	.06	.06	.01	32.	1.01	19.45	237	.02	.02	.00	30.
1.01	7.50	94	.06	.06	.01	33.	1.01	19.50	238	.02	.02	.00	28.
1.01	7.55	95	.06	.06	.01	33.	1.01	19.55	239	.02	.02	.00	25.
1.01	8.00	96	.06	.06	.01	33.	1.01	20.00	240	.02	.02	.00	21.
1.01	8.05	97	.06	.06	.01	33.	1.01	20.05	241	.02	.02	.00	20.
1.01	8.10	98	.06	.06	.01	33.	1.01	20.10	242	.02	.02	.00	17.
1.01	8.15	99	.06	.06	.01	33.	1.01	20.15	243	.02	.02	.00	17.
1.01	8.20	100	.06	.06	.00	33.	1.01	20.20	244	.02	.02	.00	16.

END-OF-PERIOD FLOW (Cont'd)

1.01	8.25	101	.06	.06	.00	30.	1.01	20.25	245	.02	.02	.00	15.
1.01	8.30	102	.06	.06	.00	34.	1.01	20.30	246	.02	.02	.00	14.
1.01	8.35	103	.06	.06	.00	34.	1.01	20.35	247	.02	.02	.00	13.
1.01	8.40	104	.06	.06	.00	34.	1.01	20.40	248	.02	.02	.00	12.
1.01	8.45	105	.06	.06	.00	34.	1.01	20.45	249	.02	.02	.00	12.
1.01	8.50	106	.06	.06	.00	34.	1.01	20.50	250	.02	.02	.00	12.
1.01	8.55	107	.06	.06	.00	34.	1.01	20.55	251	.02	.02	.00	12.
1.01	9.00	108	.06	.06	.00	34.	1.01	21.00	252	.02	.02	.00	12.
1.01	9.05	109	.06	.06	.00	34.	1.01	21.05	253	.02	.02	.00	12.
1.01	9.10	110	.06	.06	.00	34.	1.01	21.10	254	.02	.02	.00	12.
1.01	9.15	111	.06	.06	.00	34.	1.01	21.15	255	.02	.02	.00	12.
1.01	9.20	112	.06	.06	.00	34.	1.01	21.20	256	.02	.02	.00	12.
1.01	9.25	113	.06	.06	.00	34.	1.01	21.25	257	.02	.02	.00	12.
1.01	9.30	114	.06	.06	.00	34.	1.01	21.30	258	.02	.02	.00	12.
1.01	9.35	115	.06	.06	.00	34.	1.01	21.35	259	.02	.02	.00	12.
1.01	9.40	116	.06	.06	.00	34.	1.01	21.40	260	.02	.02	.00	12.
1.01	9.45	117	.06	.06	.00	35.	1.01	21.45	261	.02	.02	.00	12.
1.01	9.50	118	.06	.06	.00	35.	1.01	21.50	262	.02	.02	.00	12.
1.01	9.55	119	.06	.06	.00	35.	1.01	21.55	263	.02	.02	.00	12.
1.01	10.00	120	.06	.06	.00	35.	1.01	22.00	264	.02	.02	.00	12.
1.01	10.05	121	.06	.06	.00	35.	1.01	22.05	265	.02	.02	.00	12.
1.01	10.10	122	.06	.06	.00	35.	1.01	22.10	266	.02	.02	.00	12.
1.01	10.15	123	.06	.06	.00	35.	1.01	22.15	267	.02	.02	.00	12.
1.01	10.20	124	.06	.06	.00	35.	1.01	22.20	268	.02	.02	.00	12.
1.01	10.25	125	.06	.06	.00	35.	1.01	22.25	269	.02	.02	.00	12.
1.01	10.30	126	.06	.06	.00	35.	1.01	22.30	270	.02	.02	.00	12.
1.01	10.35	127	.06	.06	.00	35.	1.01	22.35	271	.02	.02	.00	12.
1.01	10.40	128	.06	.06	.00	35.	1.01	22.40	272	.02	.02	.00	12.
1.01	10.45	129	.06	.06	.00	35.	1.01	22.45	273	.02	.02	.00	12.
1.01	10.50	130	.06	.06	.00	35.	1.01	22.50	274	.02	.02	.00	12.
1.01	10.55	131	.06	.06	.00	35.	1.01	22.55	275	.02	.02	.00	12.
1.01	11.00	132	.06	.06	.00	35.	1.01	23.00	276	.02	.02	.00	12.
1.01	11.05	133	.06	.06	.00	35.	1.01	23.05	277	.02	.02	.00	12.
1.01	11.10	134	.06	.06	.00	35.	1.01	23.10	278	.02	.02	.00	12.
1.01	11.15	135	.06	.06	.00	35.	1.01	23.15	279	.02	.02	.00	12.
1.01	11.20	136	.06	.06	.00	35.	1.01	23.20	280	.02	.02	.00	12.
1.01	11.25	137	.06	.06	.00	35.	1.01	23.25	281	.02	.02	.00	12.
1.01	11.30	138	.06	.06	.00	35.	1.01	23.30	282	.02	.02	.00	12.
1.01	11.35	139	.06	.06	.00	35.	1.01	23.35	283	.02	.02	.00	12.
1.01	11.40	140	.06	.06	.00	35.	1.01	23.40	284	.02	.02	.00	12.
1.01	11.45	141	.06	.06	.00	35.	1.01	23.45	285	.02	.02	.00	12.
1.01	11.50	142	.06	.06	.00	35.	1.01	23.50	286	.02	.02	.00	12.
1.01	11.55	143	.06	.06	.00	35.	1.01	23.55	287	.02	.02	.00	12.
1.01	12.00	144	.06	.06	.00	35.	1.02	0.00	288	.02	.02	.00	12.

SUM 32.50 31.34 1.15 1935.
(825.)(795.)(25.)(540.54)

	PEAK	6-HOUR	24-HOUR	72-HOUR	TOTAL VOLUME
CFE	1004.	204.	66.	66.	1935.
MS	31.	.	1.	1.	541.
POWEL	15.22	32.35	32.35	32.35	32.35
HS	641.17	335.44	335.44	335.44	335.44
42-FT	101.	101.	101.	101.	101.
7-600 20 "	125.	102.	102.	102.	102.

THIS PAGE IS BEST QUALITY PRACTICABLE
FROM COPY FURNISHED TO DDC

CURRENT DEPTH	0.	7.	11.	18.	26.
CAUSEWAY	0.	63.	151.	264.	513.
ELEVATION	742.	770.	780.	790.	800.

100-YR. FLOOD SAFETY ANALYSIS

PMF

INITIAL VALUE	CAUSEWAY CREST	TOP OF DAM
770.00	772.40	
63.	63.	80.
0.	0.	263.

RATIO OF PMF	MAXIMUM RESERVOIR ELEVATION	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE	MAXIMUM OUTFLOW CFS	DURATION OVER TOP	TIME OF MAX OUTFLOW	TIME OF FAILURE
.50	772.27	0.00	79.	238.	0.00	15.03	0.00
.55	772.43	.03	80.	249.	.08	15.83	0.00
1.00	773.55	1.15	89.	320.	.92	15.75	0.00

100-YR. FLOOD SAFETY ANALYSIS

100-YR. FLOOD

INITIAL VALUE	CAUSEWAY CREST	TOP OF DAM
770.00	772.40	
63.	63.	80.
0.	0.	263.

RATIO OF PMF	MAXIMUM RESERVOIR ELEVATION	MAXIMUM DEPTH OVER DAM	MAXIMUM STORAGE	MAXIMUM OUTFLOW CFS	DURATION OVER TOP	TIME OF MAX OUTFLOW	TIME OF FAILURE
.50	771.20	0.00	79.	238.	0.00	15.42	0.00

DATE
ILME